



①1 Publication number : **0 635 794 A2**

①2

EUROPEAN PATENT APPLICATION

②1 Application number : **94305280.3**

⑤1 Int. Cl.⁶ : **G06F 17/22**

②2 Date of filing : **19.07.94**

③0 Priority : **20.07.93 JP 179233/93**
20.07.93 JP 179234/93
20.07.93 JP 179238/93
20.07.93 JP 179239/93

④3 Date of publication of application :
25.01.95 Bulletin 95/04

⑧4 Designated Contracting States :
DE FR GB IT NL

⑦1 Applicant : **CANON KABUSHIKI KAISHA**
30-2, 3-chome, Shimomaruko,
Ohta-ku
Tokyo (JP)

⑦2 Inventor : **Nagashima, Masaaki, c/o Canon**
Kabushiki Kaisha
30-2, 3-chome Shimomaruko
Ohta-ku, Tokyo (JP)
Inventor : **Yamakawa, Tadashi, c/o Canon**
Kabushiki Kaisha
30-2, 3-chome Shimomaruko
Ohta-ku, Tokyo (JP)
Inventor : **Kono, Akihiro, c/o Canon Kabushiki**
Kaisha
30-2, 3-chome Shimomaruko
Ohta-ku, Tokyo (JP)


⑦4 Representative : **Beresford, Keith Denis Lewis**
et al
BERESFORD & Co.
2-5 Warwick Court
High Holborn
London WC1R 5DJ (GB)

⑤4 Document processing apparatus and method.

⑤7 A document processing apparatus which permits the sharing of a document element in a document structure while keeping the consistency to the change of the content is provided. In a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, a document element having a content to be shared with a second document is designated from a plurality of document elements of a first document, and the content of the designated document element is defined as a content of a predetermined document element of the second document to share a common content by the first and second documents.

Further, in order to prevent a content shared by a plurality of document elements from being inadvertently broken by the edition to one document element, the document element having the shared content is detected from a document when the display of the document is commanded and it is displayed in a distinguishable manner from other portions.

FIG. 1



EP 0 635 794 A2

BACKGROUND OF THE INVENTION

Field of the Invention

The present invention relates to document processing apparatus and method for managing a plurality of documents each containing a plurality of document elements.

Related Background Art

In a past, a cut and paste method has been used as a method for defining a content of a document as a content of another document. For example, let us consider a case in which an abstract of a certain number of articles are to be prepared.

Fig. 2 shows article document data and Fig. 3 shows abstract document data. They follow the SGML description method in which a document element starts with a document element start symbol `<xxx>` and ends with a document element end symbol `</xxx>`, where xxx contains a document name of the document element. A character string between the document element start symbol and the document element end symbol represents a document element content. It is assumed that the document element comprises a document element name and a document element content. Other secondary information may also be included.

Where a content "defg, hijk" of a document element `<abstract>` of the article document data of Fig. 2 is to be quoted as it is as a content of a document element `<itemparagraph>` of the abstract document data of Fig. 3, a content "lmno." of `<itemparagraph>` is first erased, and the content "defg, hijk" of the `<abstract>` is pasted in situs by the cut and paste method.

Alternatively, it may be realized by a hyperdocument method. In this method, a link to a content of other document data is pasted from a certain portion of a document and a button 47 shown in Fig. 4 is filled in that portion. When the button is clicked, another window appears so that the content of the other document data to which the link was pasted is displayed.

However, in the cut and paste method, since the identical data are copied and present at two locations as separate data, when a common portion is corrected in either one of the article or the abstract and the both contents are to be matched, the same correction is to be made for the other. This is not effective because the same correction is to be repeated twice, and if only one is corrected, the conformity is lost.

Further, in the method of pasting the link, the above problem is solved but the button must be clicked in order to display the document data to which the link was pasted, on the display, and where multiple sharing is made in order to display it on other window than that on which the document data having the button embedded therein is displayed, the number of

windows increases and the windows overlap. Thus, the display is complex and hard to permit the grasp of a series of documents.

Further, since they share the document data including the document layouts, it is not possible to display the respective documents with required layouts.

SUMMARY OF THE INVENTION

It is a concern of the present invention to provide a document processing apparatus which permits a plurality of document elements to share contents in respective document structures while maintaining the consistency to the change of content.

It is another concern of the present invention to prevent a content shared by a plurality of document elements from being erroneously broken by the edition to one document element.

It is other concern of the present invention to discriminate shared portions and non-shared portions when a document is displayed.

It is other concern of the present invention to permit to determine whether a subject to be edited is a shared portion or not when a document is to be edited.

According to one aspect, the present invention which achieves these objectives relates to a document processing apparatus for managing a plurality of documents each containing a plurality of document element, comprising: designation means for designating, from a plurality of document elements of a first document, a document element having a content to be shared with a second document; and definition means for defining the content of the document element designated by the designation means as a content of a predetermined document element of the second document.

According to another aspect, the present invention relates to a document processing apparatus for managing a plurality of document each containing a plurality of document elements, comprising: storage means for storing document data to be used as contents of the document elements with file names; definition means for defining a command for reading the file content to each of the document elements to be used as the contents of the document data, by using the file name as an argument of the command; and control means for outputting the file content of the file name as the content of the document element when the document containing the document element having the command defined by the definition means is outputted.

According to other aspect, the present invention relates to a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising: permission means for permitting the sharing of designated ones of a plurality of document elements of a first document with the content of other document; and defini-

tion means for designating a desired one of the document elements having the sharing of content permitted by the permission means and defining the content of the designated document element as a content of a predetermined document element of a second document.

According to other aspect, the present invention relates to a document processing apparatus for managing a plurality of documents each containing a plurality of document element, comprising: designation means for designating, from a plurality of document elements of a first document, a document element having a content to be shared with a second document; separation means for separating the content of the document element designated by the designation means from the first document; first definition means for defining such that the content of the document element separated by the separation means is referred to by the first document as the content of the designated document element; and second definition means for defining such that the content of the document element separated by the separation means is referred to by the second document as a content of a predetermined document.

According to other aspect, the present invention relates to a document processing apparatus for managing a plurality of documents each containing a plurality of document elements by setting management information in each document, comprising: designation means for designating, from a plurality of document elements of a first document, a document element having a content to be shared with a second document, setting means for setting new management information to the document element designated by the designation means; control means for controlling the document element designated by the designation means to manage by the management information set by the setting means in place of the management information to the first document element; first definition means for defining to refer the management content of the management information set by the setting means as the content of the designated document element in the first document; and second definition means for defining to refer the management content of the management information set by the setting means as the content of the designated document element in the second document.

According to other aspect, the present invention relates to a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising: definition means for defining one document element content as a sharing content to be shared by a plurality of document elements; command means for commanding the display of the document; detection means for detecting the document element containing the sharing content defined by the definition means, from the document commanded by the command

means; and display control means for displaying the document commanded by the command means in a manner distinguishable from other portions of the document element detected by the detection means.

According to other aspect, the present invention relates to a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising: definition means for defining one document element content as a sharing content to be shared by a plurality of document elements; command means for commanding the edition of the document element; discrimination means for determining whether the document element designated by the designation means contains the sharing content defined by the definition means; and notification means for notifying to a user of the determination as to the sharing content by the discrimination means.

According to other aspect, the present invention relates to a document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document element, comprising the steps of: designating, from a plurality of document elements of a first document, a document element having a content to be shared with a second document; and defining the content of the designated document element as a content of a predetermined document element of the second document.

According to other aspect, the present invention relates to a document processing method in a document processing apparatus for managing a plurality of document each containing a plurality of document elements, comprising the steps of: storing document data to be used as contents of the document elements with file names, in a memory; defining a command for reading the file content to each of the document elements to be used as the contents of the document data, by using the file name as an argument of the command; and outputting the file content of the file name as the content of the document element when the document containing the document element having the command defined by the definition means is outputted.

According to other aspect, the present invention relates to a document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising the steps of: permitting the sharing of designated ones of a plurality of document elements of a first document with the content of other document; and designating a desired one of the document elements having the sharing of content permitted by the permission means and defining the content of the designated document element as a content of a predetermined document element of a second document.

According to other aspect, the present invention

relates to a document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document element, comprising: designating, from a plurality of document elements of a first document, a document element having a content to be shared with a second document; separating the content of the document element designated by the designation means from the first document; defining such that the content of the document element separated by the separation means is referred to by the first document as the content of the designated document element; and defining such that the content of the document element separated by the separation means is referred to by the second document as a content of a predetermined document.

According to other aspect, the present invention relates to a document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document elements by setting management information in each document, comprising the steps of: designating, from a plurality of document elements of a first document, a document element having a content to be shared with a second document, setting new management information to the designated document element; controlling the designated document element to manage by the set management information in place of the management information to the first document element; defining to refer the management content of the set management information as the content of the designated document element in the first document; and defining to refer the management content of the set management information as the content of the designated document element in the second document.

According to other aspect, the present invention relates to a document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising the steps of: defining one document element content as a sharing content to be shared by a plurality of document elements; commanding the display of the document; detecting the document element containing the defined sharing content from the commanded document; and displaying the command document in a manner distinguishable from other portions of the detected document element.

According to other aspect, the present invention relates to a document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising the steps of: defining one document element content as a sharing content to be shared by a plurality of document elements; commanding the edition of the document element; determining whether the designated document element

contains the sharing content defined by the definition means; and notifying to a user of the determination as to the sharing content.

Other objective and advantages besides those discussed above shall be apparent to those skilled in the art from the description of preferred embodiments of the invention which follows. In the description, reference is made to the accompanying drawings, which form a part thereof, and which illustrate examples of the invention. Such examples, however, are not exhaustive of the various embodiments of the invention, and therefore reference is made to the claims which follow the description for determining the scope of the invention.

BRIEF DESCRIPTION OF THE DRAWINGS

Fig. 1 shows a block diagram of a document processing apparatus in accordance with an embodiment of the present invention,

Fig. 2 shows an example of article document data,

Fig. 3 shows an example of abstract document data,

Fig. 4 shows an example of content definition by link,

Fig. 5 shows an example of structured document data,

Fig. 6 shows a format of an object,

Fig. 7 shows a flow chart of content sharing,

Fig. 8 shows an example of display for sharing,

Fig. 9 shows an example of display at a time of selection of a document element,

Fig. 10 shows an example of structured document data after the sharing process,

Fig. 11 shows an example of display of document data after the sharing process,

Fig. 12 shows an example of display at a time of selection of a document element,

Fig. 13 shows an example of display at a time of selection of a document element,

Fig. 14 shows an example of description of a document data,

Fig. 15 shows an example of description of a document data,

Fig. 16 shows an example of object data,

Fig. 17 shows a format of a document element object,

Fig. 18 shows an example of object data,

Fig. 19 shows a flow chart of a sharing permission declaration process,

Fig. 20 shows an example of display at a time of the sharing permission declaration process,

Fig. 21 shows a flow chart of a process for sharing a permitted content,

Fig. 22 shows a format of a share table,

Fig. 23 shows a flow chart of a sharing permission declaration process,

Fig. 24 shows an example of display at a time of the sharing permission declaration process,
 Fig. 25 shows a flow chart of a process for sharing a permitted content,
 Fig. 26 shows an example of display of a dialog window,
 Fig. 27 shows an example of sharing of a document element having an attribute,
 Fig. 28 shows a flow chart of content sharing process,
 Fig. 29 shows a flow chart of a shared content separation process,
 Fig. 30 shows an example of structured document data,
 Fig. 31 shows a store condition having a shared content separated,
 Fig. 32 shows an example of structured document data having a shared content,
 Fig. 33 shows an example of structured document data having management information,
 Fig. 34 shows an example of structured data having a shared content,
 Fig. 35 shows a block diagram of a document processing apparatus of an embodiment,
 Fig. 36 shows an example of display of document data,
 Fig. 37 shows a structure of article data,
 Fig. 38 shows a structure of abstract data,
 Fig. 39 shows a flow chart of a document display process,
 Fig. 40 shows an example of display of abstract data,
 Fig. 41 shows an example of a nesting structure of shared elements,
 Fig. 42 shows an example of display when shared elements are nested,
 Fig. 43 shows an example of display when shared elements are nested,
 Fig. 44 shows a flow chart of a document display process,
 Fig. 45 shows an example of display of document data,
 Fig. 46 shows a block diagram of a document processing apparatus of an embodiment,
 Fig. 47 shows an example of display when a shared portion is selected,
 Fig. 48 shows an example of display when a shared portion is edited,
 Fig. 49 shows a flow chart of a content update process,
 Fig. 50 shows an example of display when the updating of a shared portion is directed,
 Fig. 51 shows a flow chart of a content update process, and
 Fig. 52 shows an example of display when the updating of a shared portion is directed.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

Referring to the drawings, a construction and an operation of a document processing apparatus in accordance with the embodiments of the present invention are explained.

[Embodiment 1]

Fig. 1 shows a block diagram of a basic configuration of a document processing apparatus in accordance with one embodiment of the present invention. Numeral 1 denotes a keyboard for entering characters and commands, numeral 2 denotes a mouse for specifying an area on a display and selecting a menu, numeral 3 denotes a CPU which executes various controls and processes in accordance with programs, and numeral 4 denotes a CRT for displaying data. Numeral 10 denotes a storage for storing programs to be executed and various data, and numeral 20 denotes an auxiliary storage for permanently storing programs and data.

The storage 10 stores a document element detection program 11 for detecting a document element and a content defining program 12 for defining a content of a document element to a content of another document element, and the auxiliary storage 20 stores article data 21 and abstract data 22. The storage 10 may be shared by the auxiliary storage 20.

In the present embodiment, structured document data is handled as a memory image by an object database. Fig. 5 shows an example of article data 21 and abstract data 22 managed in the object database. Fig. 6 shows formats of a document element object and character object of Fig. 5. As seen from Figs. 5 and 6, a content of the document element is a sequence of document element objects or character objects, and a document element content storage location in Fig. 6 is a pointer to the document element content. In Fig. 6, a next pointer is one to a next document element object or character object.

In the present embodiment, the content is defined by sharing the content of other document. In the following description, it is assumed that article data is a source (src) that provides a shared content, and abstract data is a receiver (dist) that receives the shared content, and that a content "defg, hijk" of a document element <itemparagraph> first appeared in the dist is shared by the dist to set the content of the document element <itemparagraph> to "defg, hijk". A process is now explained.

Referring to a flow chart of Fig. 7, in a step S701, documents of the src and the dist are displayed on a window 41. Fig. 8 shows an example of display of the CRT 4. In Fig. 8, document data are displayed in the layout which facilitate the watching by a user, although they may be displayed with document element

start symbols and document element end symbols mixedly interposed, that is, in the forms shown in Figs. 2 and 3. In the present embodiment, the documents of the src and the dist are displayed on one window 41. For example, article data which is the document of the src is displayed at the top of the window 41 and abstract data which is the document of the dist is displayed at the bottom. The document data of the src and the dist may be identical. Numeral 42 denotes a button for directing the execution of sharing by a click of the mouse, and numeral 43 denotes a mouse cursor.

In a step S702, a document element of the src selected by a user is detected. In a step S703, a document element of the dist selected by the user is detected. The selection is effected by dragging the document element of the dist and the document element of the src by the mouse 2. Fig. 9 shows an example of display when the document elements of the src and the dist are selected by the dragging. Hatched areas in Fig. 9 are selected. The process heretofore is attained by an SGML document editor on a conventional window.

When the share button 42 is clicked, in a step S704, a document element content storage location of the document element object of the dist detected in the step S703 is changed to the document element content storage position of the document element object of the src detected in the step S702.

In this manner, the content of the document element of the dist is shared by the content of the document element of the src. In Fig. 7, the order of the step S702 and the step S703 may be reversed.

Fig. 10 shows the formats of the article data 21 and the abstract data 22 in the memory (database) after the execution of the sharing process shown in the flow chart of Fig. 7.

The content storage location of the document element `<itemparagraph>` first appeared in the dist indicates, before the execution, the storage location of the object sequence "lmn..." as shown by broken lines, but after the execution, it indicates the storage position of the object sequence "def...". Namely, the document element content is shared by the document element `<abstract>` of the src which indicates the same location.

Fig. 11 shows a status in which the both document data are displayed when the content of the document element is shared. The content of the first item of the dist has been changed to "defg, hijk".

As described above, in Fig. 8, the document data is displayed in the form which facilitate the watching by the user although it may be displayed in the forms shown in Figs. 2 and 3, that is, with the document element punctuation symbols interposed. In this case, as shown in Fig. 12, the document element may be selected by dragging the entire content of the document element, or as shown in Fig. 13, the document ele-

ment may be selected by dragging the entire document element.

Whichever form may be used for the display, when only a portion of the document element or the content of the document element is dragged, it may be determined that the document element was not selected and the sharing may not be effected, or a minimum document element which contains the selected range may be selected.

Since the content is shared, if the content of abstract of the article data 21 is changed to "defg, HIJK" for example, the content of the first item of the abstract data 22 is automatically changed to "defg, HIJK". On the other hand, if the content of the first item of the abstract data is changed, the content of the abstract of the article data is also changed.

Since only the content is shared, the shared portion may be laid out as "abstract" in the article document even after the sharing, and it may be laid out as "itemparagraph" in the abstract document. Namely, they may be displayed and printed out in the layouts which fit to the contexts of the respective documents.

[Embodiment 2]

In the Embodiment 1, the document data is explained as the object data in the memory although the present invention is not limited thereto. For example, other document content may be defined on the text data of Fig. 2 or Fig. 3.

For example, it is assumed that the content of each document element includes a text sequence of the content or a special command. The special command is "%input" which commands to read in a content of a file and has a file name as an argument.

When the sharing of the Embodiment 1 is to be effected, text data is described as shown in Fig. 14. Namely, the "%input" command is placed at the position of the content of the document element `<abstract>` and a file "sharedoc" is specified. The file "sharedoc" stores "defg, hijk". In this manner, the content of the document element `<abstract>` may be defined to the content of the other document. In order to execute the "%input" command, a method used in a document shaping system TeX may be used. Similarly, the "%input" command is inserted at the position of the content of the document element `<itemparagraph>` of the first item of the abstract data to specify the same file. Thus, the contents of the document elements of the both documents are shared through the file "sharedoc".

The description may be made as shown in Fig. 15. The document data "defg, hijk" is previously defined and it is developed at the position of the content of the document element `<itemparagraph>`. This may also be implemented in the document shaping system TeX as a macro defining function. The description of the entity reference of the SGML also corresponds

thereto. Namely, the definition may be made by previously describing that the entity "sharedoc" is "defg, hijk" and describing "&sharedoc;" instead of the content of the document. The "%input" command may be inserted between the document element start symbol and the document element end symbol and the content of the document element may be described in the file specified thereby. In this case, the object model of the Embodiment 1 may be attained by using the text description and the file.

The object model may be that shown in Fig. 16 in which the document element <itemparagraph> indicates the document element <abstract> but it actually indicates the content of <abstract>. As shown in Fig. 17, the document element object is provided with a flag to selectively indicate the pointed object (sequence) or the content of the pointed document element object depending on the content of the flag of the document element object. In Fig. 16, when the flag is "I", it indicates the content of the pointed document element object. When it indicates the content of the pointed document element object, the process may be terminated at that point to prevent the sharing if the pointed object is the character object, or the flag may be neglected so that it indicates the object itself. In the Embodiment 1, when the document element content is shared, there is no distinction on the object model between the src and the dist, but in the present embodiment, the src and the dist are distinctive.

The sharing may be made through a share object. As shown in Fig. 18, a pointer to the share object is stored at the document element content storage location in the document element object having a shared content. The share object points the document element content to be shared. This may be an object model version of the "%input" command in that the pointed item is the document element content (object sequence) or a special element which is one share object.

[Embodiment 3]

In the Embodiment 1, the windows system is used as a user interface for the sharing. In the present embodiment, the sharing is made from a command line.

A system configuration, structured document data to be handled and a format of the object are identical to those of Figs. 1, 5 and 6 of the Embodiment 1.

When the sharing is to be made, the user enters "share ddd [i][j] sss [k]" from the command line, where "ddd" is a document name of the dist, "sss" is a document name of the src, and "i", "j" and "k" are integers no smaller than 0. "ddd [i]" indicates the i-th object counted from 0 of the content of the document of the dist. Similarly, "ddd [i][j]" indicates the j-th object of the content of "ddd [i]" when the object "ddd [i]" is the

document element object. Only when all of ddd [i], ddd [i][j] and sss [k] are the document element objects, the content of the document element object "ddd [i][j]" is shared by the content of the document element object "sss [k]".

For example, in the Embodiment 1, the document element <itemparagraph> of the first item of Fig. 3 is represented by "ddd [0][1]", and the document element <abstract> of Fig. 2 is represented by "sss [1]". When "share ddd [0][1] sss [1]" is entered from the command line, the sharing of the document is effected as it is in the Embodiment 1. However, the sharing is not effected if any of ddd [i], ddd [i][j] and sss [k] is a character object. The sharing is also not effected when the integer "i", "j" or "k" is too large. It may be processed as the last object of the document element content (object sequence).

An operation process of the present embodiment may be that of Fig. 7 of the Embodiment 1 with the omission of S701. In the document element detection steps S702 and S703, the number of objects of the document element content is counted. If the object other than the document element object is detected, the process is terminated to prevent the sharing.

In the present embodiment, since the windows system is not used, the system may be constructed without regard to the specification of the windows system.

[Embodiment 4]

In the present embodiment, the document element of the src is declared as a "share permitted document element", and in the dist, "to share that document element" is declared to share the content of the document element.

A system configuration, structured document data to be handled and an object format in the present embodiment are identical to those of Figs. 1, 5 and 6 of the Embodiment 1 except that a share buffer 101 is provided in the storage 10.

The process in the present embodiment is divided into a process for declaring the share permission and a process for declaring the sharing.

Fig. 19 shows an event process when the share permission is declared. In a step S1901, a document of the src is displayed on the window 41. An example of display of the CRT 4 is shown in Fig. 20. Numeral 44 denotes a button which is displayed to indicate the share permission. When the user selects a document element by using the mouse 2, the system detects the document element in a step S1902, and when the user clicks the share permission button 44, the content storage location of the selected document element is stored in the share buffer 101 in a step S1903.

Referring to Fig. 21, an event process when the content permitted in the src is shared by the dist is explained. First, in a step S2101, a document of the dist

is displayed on the window 41. In a step S2102, a document element selected by the user is detected, and when the share button 42 is clicked, the document content storage location of the document element object is changed to the content of the share buffer 101 in a step S2103. In the step S2103, if the share buffer 101 contains non-permitted value, for example, "0", the process is terminated and the sharing is not effected. The process of the present embodiment has thus been described.

In accordance with the present embodiment, when the contents of a number of document elements are to be shared by the content of one document element, the share permission is declared so that the pointers to the contents of the document elements are stored in the share buffer and the document element of the dist is detected. Accordingly, troublesome process of displaying both documents of the src and the dist and selecting the both document elements by the mouse are not necessary and the process is efficient. Further, in the share permission declaration, the provider of the sharing document may specify the portion to which the sharing is permitted so that undue sharing by others may be prevented.

[Embodiment 5]

In the Embodiment 4, the shared buffer is used, but in the present embodiment, the content storage location (pointer) of the document element for which the share permission was declared is stored in the share table.

A system configuration, structured document data to be handled and an object format in the present embodiment are identical to those of Figs. 1, 5 and 6 of the Embodiment 1 except that a share table 102 is provided in the storage 10.

Fig. 22 shows a format of the share table 102. The share table 102 is in a form of dictionary which comprises key words (variable names) and values (document element content storage locations).

Fig. 23 shows an event process when the share permission is declared. In a step S2301, a document of the src is displayed on the window 41. When the user selects a document element by using the mouse 2, the system detects the document element in a step S2302. When the user clicks the share permission button 44, a dialog window 45 is displayed on the CRT 4 in a step S2303. An example of display of the CRT 4 is shown in Fig. 24. When a variable name is entered from the dialog window 45, the content storage location of the document element selected in the step S2302 is stored in the share table 102 together with the variable name. If the same variable name has already been registered in the share table 102, the value thereof, that is, the document element content storage location is updated.

Fig. 25 shows a process for sharing.

In a step S2501, the document of the dist is displayed on the window 41. In a step S2502, a document element selected by the user is detected, and when the share button 42 is clicked, the dialog window 46 is displayed on the CRT 4 in a step S2503. An example of display of the CRT 4 is shown in Fig. 26. When the user specifies a variable name from the dialog window to indicate which document element content is to be shared, the document element content storage location (pointer) of the document element object selected in the step S2502 is changed to the value introduced from the share table 102 through the variable name, that is, the content of the document element content storage location in a step S2504. If the corresponding variable name is not detected in the share table 102 in the step S2504, the process is terminated and the sharing is not effected. The process of the present embodiment has thus been described.

In accordance with the present embodiment, the document element for which the share permission has been declared can be stored by using the document element content storage location as a variable and the shared document element can be selected through the variable.

In the embodiments described above, since the document element content is shared, the shared portion of the dist is changed when the shared portion of the src is changed so that the change may be made while keeping the consistency of the document. Other information than the document element such as the document element name is not shared but only the content of the document element is shared. Accordingly, even if the sharing is made with the document element of other document, the sharing may be attained without changing the logical structure of the document currently handled. Namely, in the article document, the shared portion may be handled as the abstract and in the abstract document, the shared portion may be handled as the itemparagraph. Accordingly, as shown in Fig. 11 of the Embodiment 1, it may be laid out as the abstract of the article document or the itemparagraph of the abstract document.

When the document element has an attribute, it may be changed without changing the attribute value as the document element name is. Fig. 27 shows an example thereof. In Fig. 27, a patent document and an article document are shown and both share a content of a document element <fig>. The document element <fig> has an ID assigned as an attribute. A document element <body> describes a drawing actually outputted. The drawing is drawn by sequentially outputting symbols (characters) surrounded by characters "".

In Fig. 27, an ID "sample" is assigned to the document element <fig> of the document "patent", and an ID "system" is assigned to the document element <fig> of the document "article". When a figure number is to be entered to the fig, it may be referred by "<re-

fid="sample">" in the document "patent" and by "<refid="system">" in the document "article". If the document element <fig> itself is shared with the document element <fig> of the document "patent" as the dist and the document element <fig> of the document "article" as the src, the attribute value of the document element <fig> of the document "patent" will be "system". Accordingly, in the document "patent", the reference by "<refid="sample">" cannot be attained and all values of "refid" must be updated. However, in the present embodiment, since only the content is updated without changing the attribute, the problem which is encountered in sharing the document element itself is avoided.

[Embodiment 6]

A system configuration of the present embodiment is identical to that of the Embodiment 1 except that the storage 10 is provided with a shared content separation program 15 instead of the content defining program 12. It is assumed that the document data is described in a text form and stored in a file. Article data 21 is stored by a file name "art" and abstract data is stored by a file name "abst".

Referring to a flow chart of Fig. 28, steps S2801 - S2803 are essentially identical to the steps S701 - S703 of Fig. 7 except that the selection of the document in the step S2801 is effected by entering the file name and reading the file.

When the share button is clicked, the shared content separation process is started in a step S2804. Referring to a flow chart of Fig. 29, the process is explained. In a step S2901, whether the content of the document selected in the src is the shared data or not is determined. In the present embodiment, as will be explained later, the shared data is made independent from the document data. Accordingly, whether it is the shared data or not is determined by examining whether the description is to refer other data or not. If the content is not shared, it is the data of the article data 21 and the decision is "no", and the process proceeds to a step S2902. If the content is shared, the description is to refer the shared data in a step to be described later and the process proceeds to a step S2904.

In the step S2902, the content of the document element selected in the src is extracted, and it is stored in shared data area 23 (not shown) newly allocated to the auxiliary storage 20 as a storage location. In the present embodiment, "defg, hijk" is stored as the shared data 23. A file name of the shared data 23 is generated. For example, a numeral is added to the end of the document file name "art" of the src to generate "art01".

In a step S2903, the description is changed to refer the shared data 23 instead of the content of the document element selected in the src. For example, in the SGML, description of reference to entity may be

used. In the document declaration portion, the entity is described to use the content of the file "art01" and "& art01;" is described instead of the document element content so that the content of the file referred to may be handled as the document data. Specifically, the portion "defg, hijk" of the article data stored in the file "art" is changed to "& art01;".

In a step S2904, the description is changed in the dist to refer the shared data 23 instead of the content of the selected document element as it is in the src. Specifically, the portion "1mno." of the article data stored in the file "abst" is changed to "& art01;".

In this manner, the content of the document element in the dist and the content of the document element in the src are shared by referring the same content separately stored. When the documents of the src and the dist which refer the content of the shared data 23 are subsequently redisplayed on the window 41, "defg, hijk" is displayed as shown in Fig. 9. When "defg, hijk" in the src which is shared with the dist is changed to "defg,HIJK", the content of the shared data 23 is changed to "defg,HIJK". Accordingly, when the document is redisplayed in the dist, the content of the changed shared data 23 is referred to so that the item 1 of the itemized document is changed to "[ABC]defg,HIJK".

[Embodiment 7]

In the Embodiment 6, the shared portion is selected in the src and the dist to effect the shared content separation process at the timing of the share command.

In the present embodiment, a first half of the shared content separation process is effected at the timing of the selection of the object to be shared in the src and the command to offer it as the shared data. The timing may be generated by depressing an "offer" button for commanding the offer.

In this case, the steps S2901 to S2903 of the flow chart of Fig. 29 are executed. The reference address (for example, the file name of the shared data) is stored in the share buffer 24 (not shown) in the storage 20. A portion of the document in the dist whose content is to be rendered identical to that of the shared data is selected, and a latter half of the shared content separation process is effected at the timing of the command to share with the designated data. In this case, a step S2904 of the flow chart of Fig. 29 is executed. The reference address is that stored in the share buffer 24.

In accordance with the present embodiment, when the contents of a number of document elements are to be shared with the content of one document element, the share permission is declared so that the pointer to the document element content is stored in the share buffer, and the document element in the dist is detected. Accordingly, the troublesome process of displaying the both documents of the src and the dist

and selecting the both document elements by the mouse is not necessary and the process is efficient.

Further, when the share permission is declared, the shared document provider may designate the portion to be shared to prevent undue sharing with others.

[Embodiment 8]

In the previous Embodiments 6 and 7, the document data is described in the text form and stored in the file. On the other hand, in the present embodiment, persistent data in a memory image form is stored in the object database.

Fig. 30 shows the article data 21 and the abstract data 22 managed in the object database.

The article data 21 and the abstract data 22 are allocated to different segments 51 and 52 for management. Each document element data has an identification code. Data for a document route has an identification code "DOCUMENT" and an element name representing a type of the document. The article data has an element name "article". It also has a pointer to the content of the document. The pointer points to a document element which is a first content element.

The document element includes a composite document element having a content therein and a character element which is a terminal. The former has an identification code "NODE" and the latter has an identification code "CHAR". The composite document element has a pointer to a next element, an element name representing a type of element, and a pointer to a content of the element. A first document element has an element name "title", a pointer to a composite document element having a document element name "abstract" as a pointer to the next element, and a pointer to characters as the content. The character element has a pointer to the next element and a character code. The chaining of the pointers terminates when the pointer value is "0". The process of the present embodiment basically follows the flow charts of Figs. 28 and 29 shown in the Embodiment 6 except that the method for referring the storage location and the method for changing are modified.

In a step S2901, whether the reference has been made or not is determined. If the data of the identical segment is pointed to, it is determined that the reference has not been made, and if the data of different segment is pointed to, it is determined that the reference has been made. If the reference has not been made, the process proceeds to a step S2902. In the separation storage, a new segment 53 is allocated and the content of the document element selected in the src is copied thereto. A transient data storage status of the database is shown in Fig. 31.

In a step S2903, the pointer to document element content is replaced to the data in the newly allocated

segment 53 in the src. In a step S2904, a pointer to the content of the document element selected in the dist is replaced to the data in the newly allocated segment 53. A storage status of the replaced database is shown in Fig. 32. If it is determined in the step S2901 that the reference has been made, the process proceeds to a step S2904 where the pointer to the document content of the dist is replaced. In accordance with the present embodiment, the processing speed is improved since the replacement is done by the memory image without using the file.

[Embodiment 9]

In the Embodiment 8, the respective documents are stored in different segments for management. The management may be made without changing the storage locations by affixing management information to the heads of the respective data.

Fig. 33 shows a data storage format having management information 61 and 62 affixed to the heads of a set of data.

A process therefore is basically identical to that of the previous embodiment. In the shared content separation process, management information 63 is generated instead of the allocation of the new segment and the shared content is reconnected thereto, and the management information 63 is pointed from the document elements of the src and the dist. A result thereof is shown in Fig. 34. In the present embodiment, it is not necessary to change the data storage location and the sharing is attained by mere replacement of the pointer. Thus, the processing speed is improved.

In this manner, a plurality of document elements may share the same content while keeping the consistency of the content, and each document element may have the content to be shared with other in the document structure of each document element.

[Embodiment 10]

Fig. 36 shows a document with the shared document element. In this example, the article data and the abstract data share "defg, hijk". Since the identical data is not always shared, this display format cannot discriminate whether it is shared data or not on the display. When only one document data is displayed, it is not clear whether a certain portion is shared with other or not. As a result, the shared portion might be changed without knowing it so that other document might be inadvertently broken.

In the present embodiment, the document data is displayed while the shared portions and the non-shared portions are made identifiable.

Fig. 35 shows a system configuration of the present embodiment. The hardware configuration is identical to that of the Embodiment 1 except that the con-

tent defining program 12 is replaced by a sharing determination program 13, a sharing display program 14 and a document element display program 15.

Fig. 37 shows an example of the article data 21 managed in the object database. The abstract data 22 is also managed. The article data 21 has a document object 2110 as a route. The document object 2110 has an object type "DOCUMENT", a document type "article" and a pointer to a document content object 2111 which represents the content of the document. The document content object 2111 has an object type "content", a reference count "1" and the substance of the content as a pointer to the head of the content. Document elements or a character sequence having staggered contents may be defined as the content. In the present example, the document content object 2111 points to a document element object 2112 which is the first element of the content. The reference count represents the number of document elements which points to the document content object as the content of the document element. Since the document element content object 2111 consists of the content of only the document object 2111, the reference count is "1".

The document element object 2112 has an object type "ELEMENT", a pointer to an element which represents a succeeding content and a pointer to an object which represents the content of the document element. In the present example, a document element object 2113 of the element name "abstract" is pointed as the succeeding content, and a document element content object 2114 is pointed. The document element content object 2114 points to a character object 2115 which is the content of the head as the substance of the content.

The character object 2115 has an object type "CHAR", a pointer to an element which is a succeeding content and a character code "A". A character object 2116 having a character code "B" is pointed as the succeeding content.

In the present embodiment, it is assumed that the content of the document element of the document element name "abstract" of the article data and the content of the document element of the document element name "itemparagraph" which first appeared in the abstract data are shared. The article data format and the abstract data format are shown in Fig. 38.

A document element content object 2118 which indicates "defg, hijk" is pointed by both of the document element 2113 of the element name "abstract" of the article data and the document element 2217 of the element name "itemparagraph" first appeared in the abstract data. A reference count of a document element content object 2118 is "2".

Referring to a flow chart of Fig. 39, a document display process of the present embodiment is explained. The display of the abstract data 22 shown in Fig. 38 is explained.

First, the abstract data 22 is scanned. In a step S3901, a document element object is detected. If it is not detected and the document data is over, the process is terminated. In a step S3902, the sharing determination program 12 is used to determine whether the content of the detected document element is shared with other document element content. This is determined by examining whether the reference count of the document element content object pointed by the document element object is two or larger or not. If it is two or larger, it means that the contents are shared. If the sharing is detected in the step S3902, the process proceeds to a step S3903 where the shared portion is displayed by the sharing display program 14. First, a character sequence "<share>" is displayed and then the document element content is displayed. The display and the printout of the document element content in a certain layout may be implemented by the prior art SGML technology. Finally, a character sequence "</share>" is displayed to terminate the sharing display process. On the other hand, if the sharing is not detected in the step S3902, the process proceeds to a step S3904 where the mere document element content is displayed. The process returns to the step S3901 to execute the detection of the next document element. The process has thus been described.

Fig. 40 shows a display of the abstract data 22. Since the content of the shared document element is surrounded by the character sequence "<share>" and "</share>", the shared portion can be readily identified.

A shared document element might be in the content of a shared document element, that is, the shared portion might be nested. For example, it is assumed that the shared document element content includes an enhanced document element which is shared with a portion of an index in the article data. This is illustrated in Fig. 41.

Fig. 41 indicates that a document element of a document name "emphasis" is present between "e" and "f" of a shared document element content "defg, hijk", and a content "XYZ" thereof is shared with a content of a document element of a document element name "keyword" in the index of the article data.

The sharing display program 13 may display the character sequence "<share>" as well as the depth of sharing. For example, it is displayed as shown in Fig. 42. In Fig. 42, the depth of the sharing nesting is displayed by representing the character sequences "<share>" and "</share>" as "<share1>", "</share1>", "<share2>", "</share2>". This may be implemented by providing a sharing nesting counter 103 (not shown) in the storage 10 to manage the depth of the sharing. When the content of the shared document element is displayed, it may be surrounded by special characters such as "◇" and "◇". The depth of the sharing nesting may be represented by the number of continuous special characters. When the

document data is displayed in a fully marked-up form of the SGML, the use of the special characters to surround the shared portion will facilitate the watching. An example of display is shown in Fig. 43.

[Embodiment 11]

In the present embodiment, a background color of the shared portion is changed on the display. A system configuration and document data in the present embodiment are identical to those of Figs. 35 and 37 of the Embodiment 10.

Referring to Fig. 44, a process is explained. In a step S4401, the abstract data 22 is displayed on the CRT 4. In a step S4402, a document element is detected from the abstract data 22. In a step S4403, whether the document element content is shared by other document content or not is determined. The determination method is identical to the step S3902 of the Embodiment 10 in Fig. 39.

In a step S4404, the background color of the shared document element content portion is displayed in yellow, for example. Preferably, it is distinguished from a color for designating a range by dragging. The association of the document element object in the memory to the range of the displayed document content may be implemented by a structure edit of the SGML. The change of the background color is implemented in the X window program. An example of display is shown in Fig. 45. In Fig. 45, the yellow background area is hatched. Instead of changing the background color as is done in the present embodiment, a foreground color may be changed.

When a color display is not used, an underscore may be drawn to the displayed shared document element content. Where a bit map display is used, it may be surrounded by a frame. When the sharing nesting is present, the background color may be changed depending on the depth of the sharing nesting.

In the present embodiment, since the special characters or character sequences other than the content information are not included in the displayed document, the difficulty in reading the document data is avoided. Further, whether it is the shared document element or not may be readily determined without checking the beginning or the end of the document element content.

In accordance with the embodiments described above, whether the portion of the document element content is shared with the content of other document element or not can be clearly determined. Accordingly, the portion which, when it is changed, will affect to other document can be clearly identified and undue change of the content to break the other shared document can be prevented.

[Embodiment 12]

In the above embodiment, the shared portion and the non-shared portion are distinguished when the document is displayed. In the present embodiment, the shared portion is informed to the operator when it is selected for edition.

It is assumed that while a display of Fig. 36 is made, "de" of "defg, hijk" of the document "art" is selected. This may be implemented by dragging the character sequence by the prior art mouse, and the selected portion is displayed in a distinguishable manner. An example of display is shown in Fig. 48 in which the selected area is hatched.

A character sequence, for example, "HI" previously copied in a common area such as a clip board is substituted by so-called pasting to change "defg, hijk" to "defg, Hijk". As shown in Fig. 48, "defg, hijk" of the document "abst" is also changed to "defg, Hijk". The change for other portions may be implemented in a similar manner.

Fig. 46 shows a system configuration of the present embodiment. The hardware configuration is identical to that of the Embodiment 1 except that the storage 10 has a sharing determination program 13, a content updating display program 17 and a sharing notification program 18.

A process of the present embodiment for selecting the update portion of the document content and substitute it by a new character sequence is explained. The selection of document which includes the portion of the document to be updated and the direction to substitute by the character sequence may be implemented by the prior art method. The substitution process for the direction may be implemented in the same manner as that described in the above embodiment.

It is assumed that in the data structure shown in Fig. 38, the substitution of the character sequence is commanded. The control is shifted to the content update program 17. Referring to a flow chart of Fig. 49, the content update process is explained.

In a step S4901, the selected portion is checked to detect which partial sequence of the content of the document element object it belongs to. This may be implemented by the prior art structure or document handling technique.

Then, in a step S4902, whether the detected document element content is shared with other document element content or not by using the sharing determination program 13. For example, the sharing determination program 13 determines the sharing when the reference count of the document element content object which is pointed by the document element object is two or larger, and determines as non-sharing if the count is smaller than two.

Then, if the sharing is determined in the step S4902, the process proceeds to a step S4904, and if

the non-sharing is determined, the process proceeds to a step S4905.

In the step S4904, the sharing of the object to be updated is informed by using the sharing notification program 18. For example, the sharing notification program 18 displays an interactive window as shown in Fig. 50 to inquire to the operator whether the updating of the document is to be continued or not. It waits until an "OK" button 48 is depressed, and when it is depressed, it returns to a call process. In a step S4905, the conventional content substitution process is carried out and the process is terminated and return to the call process.

In this manner, when the operator attempts to change the shared portion, the interactive window is outputted and the sharing is notified.

[Embodiment 13]

In the above embodiment, when the updating of the shared portion is requested, the interactive window is displayed to notify that it is the shared portion. Alternatively, the content updating program which notifies by ringing a buzzer may be used. Where an audio output is available, announcement of "It is shared" may be used. Further alternatively, the display may be temporarily switched such as reversal.

[Embodiment 14]

The present embodiment differs in that it uses a content update program 171 (not shown) instead of the content update program 17, and uses a sharing notification program 181 (not shown) instead of the sharing notification program 18. The process of the present embodiment up to the command to the substitution of the character sequence and the shift of the control to the content updating program 171 is identical to that of the Embodiment 12.

A process flow chart of the content updating program 171 of the present embodiment differs only in part from the process flow chart of the content updating program 17 shown in Fig. 49. This is explained with reference to a flow chart of Fig. 51.

Steps S5001 to S5003 are identical to the steps S4902 to S4903.

In a step S5004, the sharing of the object to be updated is notified by using the sharing notification program 181. The sharing notification program 181 returns an operator indication as a return value. For example, the sharing notification program 181 display the interactive window as shown in Fig. 52 to inquire to the operator whether the updating of the document is to be continued or not. It waits until the "OK" button 48 or a "cancel" button 49 is depressed, when it returns the result. The display and the button entry may be implemented by the prior art technology. Next to the step S5004, the process proceeds to a step

S5006. The process is switched in accordance with the return value at the step S5004. Namely, if the return value is "OK", the process proceeds to a step S5005, and if it is "cancel", the process is terminated and returns to the call process. In the step S5005, the content substitution process is executed as it is in the step S4905 of the Embodiment 12 and the process is terminated and returns to the call process.

In accordance with the present embodiment, when the operator attempts to update the shared portion, the interactive window is outputted and the sharing is notified and the inquiry is immediately made as to continue the updating. Thus, the operator may suspend the sharing at this moment if he/she has not noticed the sharing before so that inadvertent updating is prevented.

In accordance with the present embodiment, when the portion which is shared with other document element is to be updated, the sharing is notified so that the undesired updating which may affect to other document element can be avoided, and the updating may be executed after the confirmation of the sharing.

Although the present invention has been described in its preferred form with a certain degree of particularity, many apparently widely different embodiments of the invention can be made without departing from the spirit and scope thereof. It is to be understood that the invention is not limited to the specific embodiments thereof except as defined in the appended claims.

Claims

1. A document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising:
 - designation means for designating, from a plurality of document elements of a first document, a document element having a content to be shared with a second document; and
 - definition means for defining the content of the document element designated by said designation means as a content of a predetermined document element of the second document.
2. A document processing apparatus according to Claim 1 further comprising:
 - display control means for displaying the first and second documents;
 - said designation means designating on the display the document element having the content to be shared with the second document, from the displayed first document; and
 - said definition means designating on the display the predetermined document element from the displayed second document and defin-

ing the content of the document element designated by said designation means as the content of the predetermined document element.

3. A document processing apparatus according to Claim 1 wherein said designation means designates, by description in a command, the document element in the first document having the content to be shared with the second document and the predetermined document element in the second document.
4. A document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising:
 - storage means for storing document data to be used as contents of the document elements with file names;
 - definition means for defining a command for reading the file content to each of the document elements to be used as the contents of the document data, by using the file name as an argument of the command; and
 - control means for outputting the file content of the file name as the content of the document element when the document containing the document element having the command defined by said definition means is outputted.
5. A document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising:
 - permission means for permitting the sharing of designated ones of a plurality of document elements of a first document with the content of other document; and
 - definition means for designating a desired one of the document elements having the sharing of content permitted by said permission means and defining the content of the designated document element as a content of a predetermined document element of a second document.
6. A document processing apparatus according to Claim 5 further comprising:
 - storage means for storing a storage location of the document element having the sharing permitted by said permission means; and
 - said definition means designating the document element based on the storage location stored in said storage means.
7. A document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising:
 - designation means for designating, from a plurality of document elements of a first document, a document element having a content to be

shared with a second document;

separation means for separating the content of the document element designated by said designation means from the first document;

first definition means for defining such that the content of the document element separated by said separation means is referred to by the first document as the content of the designated document element; and

second definition means for defining such that content of the document element separated by said separation means is referred to by the second document as a content of a predetermined document.

8. A document processing apparatus according to Claim 7 further comprising:
 - display control means for displaying the first and second documents; and
 - second designation means for designating a document element of the second document to be shared with the content of the document element designated by said designation means;
 - said designation means designating the document element from the first document displayed by said display control means; and
 - said second designation means designating the document element from the second document displayed by said display control means.
9. A document processing apparatus according to Claim 7 further comprising:
 - pointer storage means for storing a pointer to the document element to be shared;
 - said pointer storage means storing a pointer to the document element separated by said separation means; and
 - said second definition means defining the content of the document element based on the pointer stored in said pointer storage means.
10. A document processing apparatus for managing a plurality of documents each containing a plurality of document elements by setting management information in each document, comprising:
 - designation means for designating, from a plurality of document elements of a first document, a document element having a content to be shared with a second document;
 - setting means for setting new management information to the document element designated by said designation means;
 - control means for controlling the document element designated by said designation means to manage by the management information set by said setting means in place of the management information to the first document element;

first definition means for defining to refer the management content of the management information set by said setting means as the content of the designated document element in the first document; and

second definition means for defining to refer the management content of the management information set by said setting means as the content of the designated document element in the second document.

11. A document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising:

definition means for defining one document element content as a sharing content to be shared by a plurality of document elements;

command means for commanding the display of the document;

detection means for detecting the document element containing the sharing content defined by said definition means, from the document commanded by said command means; and

display control means for displaying the document commanded by said command means in a manner distinguishable from other portions of the document element detected by said detection means.

12. A document processing apparatus according to Claim 11 wherein said display control means displays the detected document element with specified characters or character sequences added before and after the document element.

13. A document processing apparatus according to Claim 11 wherein said display control means displays the detected document element in a different form than that for other portions.

14. A document processing apparatus according to Claim 11 wherein the documents are nested with respect to the sharing of the document element content, said detection means determined the depth of the nesting, and said display control means distinguishably displays the depth of the nesting.

15. A document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising:

definition means for defining one document element content as a sharing content to be shared by a plurality of document elements;

command means for commanding the editing of the document element;

discrimination means for determining whether the document element designated by

said designation means contains the sharing content defined by said definition means; and

notification means for notifying to a user of the determination as to the sharing content by said discrimination means.

16. A document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising the steps of:

designating, from a plurality of document elements of a first document, a document element having a content to be shared with a second document; and

defining the content of the designated document element as a content of a predetermined document element of the second embodiment.

17. A document processing method in a document processing apparatus for managing a plurality of document each containing a plurality of document elements, comprising the steps of:

storing document data to be used as contents of the document elements with file names, in a memory;

defining a command for reading the file content to each of the document elements to be used as the contents of the document data, by using the file name as an argument of the command; and

outputting the file content of the file name as the content of the document element when the document containing the document element having the command defined by said definition means is outputted.

18. A document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising the steps of:

permitting the sharing of designated ones of a plurality of document elements of a first document with the content of other document; and

designating a desired one of the document elements having the sharing of content permitted by said permission means and defining the content of the designated document element as a content of a predetermined document element of a second document.

19. A document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising:

designating, from a plurality of document elements of a first document, a document ele-

ment having a content to be shared with a second document;

separating the content of the document element designated by said designation means from the first document;

defining such that the content of the document element separated by said separation means is referred to by the first document as the content of the designated document element; and

defining such that content of the document element separated by said separation means is referred to by the second document as a content of a predetermined document.

20. A document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document elements by setting management information in each document, comprising the steps of:

designating, from a plurality of document elements of a first document, a document element having a content to be shared with a second document,

setting new management information to the designated document element;

controlling the designated document element to manage by the set management information in place of the management information to the first document element;

defining to refer the management content of the set management information as the content of the designated document element in the first document; and

defining to refer the management content of the set management information as the content of the designated document element in the second document.

21. A document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising the steps of:

defining one document element content as a sharing content to be shared by a plurality of document elements;

commanding the display of the document; detecting the document element containing the defined sharing content from the commanded document; and

displaying the commanded document in a manner distinguishable from other portions of the detected document element.

22. A document processing method in a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, comprising the steps of:

defining one document element content as

a sharing content to be shared by a plurality of document elements;

commanding the edition of the document element;

determining whether the designated document element contains the sharing content defined by said definition means; and

notifying to a user of the determination as to the sharing content.

FIG. 1




FIG. 2

```

<article>
<title>ABC
</title><abstract>defg,hijk
</abstract><body>
<section><header>Introduction
</header><paragraph>
.....
.....
.....
</body>
</article>

```

FIG. 3

```

<articlelist>
<item>
<itemhead>ABC
</itemhead><itemparagraph>lmno.
</itemparagraph>
</item><item>
<itemhead>abc
</itemhead><itemparagraph>pqrs.
</itemparagraph>
</item>...
.....
.....
</articlelist>

```

FIG. 4






FIG. 6



DOCUMENT ELEMENT OBJECT



CHARACTER OBJECT

FIG. 5





FIG. 7




FIG. 8




FIG. 9




FIG. 10




FIG. 11




FIG. 12

```

<article>
<title>ABC
</title><abstract> defg, hijk
</abstract><body>
<section><header>Introduction
</header><paragraph>
.....
.....
.....
</body>
</article>

```

FIG. 13

```

<article>
<title>ABC
</title> <abstract> defg, hijk
</abstract> <body>
<section><header>Introduction
</header><paragraph>
.....
.....
.....
</body>
</article>

```

FIG. 14




FIG. 15




FIG. 16




FIG. 17




FIG. 19




FIG. 18




FIG. 20




FIG. 21




FIG. 22

VARIABLE NAME	DOCUMENT ELEMENT CONTENT STORAGE LOCATION
<div data-bbox="646 1543 678 1726" style="text-align: center;"> { </div>	<div data-bbox="1003 1543 1036 1726" style="text-align: center;"> { </div>
KEY WORD	VALUE

FIG. 23




FIG. 25




FIG. 24




FIG. 26





FIG. 27

```

<patent>
<paragraph>... figure<refid="sample">...
</paragraph>
<fig id="sample">system configuration
diagram<body>

```



```


</body>
</fig>
.....
</patent>

```

```

<article>
<paragraph>... figure<refid="system">...
</paragraph>
<fig id="system">system configuration
diagram<body>

```



```

</body>
</fig>
.....
</article>

```

FIG. 28




FIG. 29




FIG. 30




FIG. 31




FIG. 32





FIG. 33

21



22





FIG. 34

21



22




FIG. 35




FIG. 36




FIG. 37




FIG. 38




FIG. 39




FIG. 40

- [ABC] <share>defg, hijk. </share>
- [abc] pqrs.
-

FIG. 42

- [ABC] <share1>de<emphasize><share2>XYZ</share2></emphasize>fg, hijk. <share1>
- [abc] pqrs.
-

FIG. 43

```

<articlelist>
  <item>
    <itemhead>ABC
    </itemhead><itemparagraph> ◇ de<emphasize>◇◇ XYZ ◆◆
    </emphasize>fg, hijk. ◆
    <itemparagraph>
    </item><item>
    </itemhead>abc
    </itemhead><itemparagraph>pqrs.
    </itemparagraph>
    </item>...
    .....
    .....
  </articlelist>

```


FIG. 41




FIG. 44





FIG. 46




FIG. 47




FIG. 48




FIG. 49




FIG. 50




FIG. 51





FIG. 52





⑪ Publication number : **0 635 794 A3**

⑫ **EUROPEAN PATENT APPLICATION**

⑰ Application number : **94305280.3**

⑤① Int. Cl.⁶ : **G06F 17/22**

⑰ Date of filing : **19.07.94**

③① Priority : **20.07.93 JP 179233/93**
20.07.93 JP 179234/93
20.07.93 JP 179238/93
20.07.93 JP 179239/93

④③ Date of publication of application :
25.01.95 Bulletin 95/04

⑧④ Designated Contracting States :
DE FR GB IT NL

⑧⑧ Date of deferred publication of search report :
18.10.95 Bulletin 95/42

⑦① Applicant : **CANON KABUSHIKI KAISHA**
30-2, 3-chome, Shimomaruko,
Ohta-ku
Tokyo (JP)

⑦② Inventor : **Nagashima, Masaaki, c/o Canon Kabushiki Kaisha**
30-2, 3-chome Shimomaruko
Ohta-ku, Tokyo (JP)
Inventor : **Yamakawa, Tadashi, c/o Canon Kabushiki Kaisha**
30-2, 3-chome Shimomaruko
Ohta-ku, Tokyo (JP)
Inventor : **Kono, Akihiro, c/o Canon Kabushiki Kaisha**
30-2, 3-chome Shimomaruko
Ohta-ku, Tokyo (JP)


⑦④ Representative : **Beresford, Keith Denis Lewis et al**
BERESFORD & Co.
2-5 Warwick Court
High Holborn
London WC1R 5DJ (GB)

⑤④ **Document processing apparatus and method.**

⑤⑦ A document processing apparatus which permits the sharing of a document element in a document structure while keeping the consistency to the change of the content is provided. In a document processing apparatus for managing a plurality of documents each containing a plurality of document elements, a document element having a content to be shared with a second document is designated from a plurality of document elements of a first document, and the content of the designated document element is defined as a content of a predetermined document element of the second document to share a common content by the first and second documents.

Further, in order to prevent a content shared by a plurality of document elements from being inadvertently broken by the edition to one document element, the document element having the shared content is detected from a document when the display of the document is commanded and it is displayed in a distinguishable manner from other portions.

FIG. 1



EP 0 635 794 A3



European Patent
Office

EUROPEAN SEARCH REPORT

Application Number
EP 94 30 5280

DOCUMENTS CONSIDERED TO BE RELEVANT			
Category	Citation of document with indication, where appropriate, of relevant passages	Relevant to claim	CLASSIFICATION OF THE APPLICATION (Int.Cl.6)
X	EP-A-0 319 232 (XEROX) 7 June 1989 * the whole document *	1-22	G06F17/22
P,X	EP-A-0 578 207 (MICROSOFT) 12 January 1994 * page 2, line 48 - page 3, line 14 * * page 7, line 41 - page 8, line 25; claim 1 *	1	
A	EP-A-0 444 669 (HITACHI) 4 September 1991 * column 32, line 34 - column 33, line 30 *	1,4,5,7,10,19	
A	EP-A-0 462 915 (IBM) 27 December 1991 * the whole document *	1-22	
A	WO-A-91 08538 (KODAK) 13 June 1991 * the whole document *	1-22	
A	COMPUTER, vol. 21, no. 1, January 1988 NEW YORK, US, pages 61-69, XP 000052069 J.H. SCHLICHTER ET AL 'FolioPub: A Publication Management System' * page 64 *	1-22	
			TECHNICAL FIELDS SEARCHED (Int.Cl.6)
			G06F
The present search report has been drawn up for all claims			
Place of search THE HAGUE		Date of completion of the search 11 August 1995	Examiner Pottiez, M
CATEGORY OF CITED DOCUMENTS X : particularly relevant if taken alone Y : particularly relevant if combined with another document of the same category A : technological background O : non-written disclosure P : intermediate document T : theory or principle underlying the invention E : earlier patent document, but published on, or after the filing date D : document cited in the application L : document cited for other reasons & : member of the same patent family, corresponding document			

EPO FORM 1501 (03.92) (P04C01)

**This Page is Inserted by IFW Indexing and Scanning
Operations and is not part of the Official Record**

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

- ☐ BLACK BORDERS
- ☐ IMAGE CUT OFF AT TOP, BOTTOM OR SIDES
- ☐ FADED TEXT OR DRAWING
- ☐ BLURRED OR ILLEGIBLE TEXT OR DRAWING
- ☐ SKEWED/SLANTED IMAGES
- ☐ COLOR OR BLACK AND WHITE PHOTOGRAPHS
- ☐ GRAY SCALE DOCUMENTS
- ☐ LINES OR MARKS ON ORIGINAL DOCUMENT
- ☐ REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY
- ☐ OTHER: _____

IMAGES ARE BEST AVAILABLE COPY.

As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.